

BANGALORE DIVISION.

Dated 2nd July 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 20th July 1929, for constructing a Dispensary Building with quarters for the Staff at Anagondanahalli, Hoskote Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of January 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3a. Percentages less or above estimated rates will not be accepted.

4. Each tender must be accompanied by a deposit of Rupees two hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Constructing Dispensary Building at Anagondanahalli," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for construction of Dispensary Building with Staff Quarters at Anagondanahalli, Hoskote Taluk.

No.	Items of work	Per	Quantity	Rate
	<i>Local Fund Dispensary.</i>			Rs.
1	Earthwork excavation, foundation and filling in basement level with consolidation.	C.yd.	78	
2	Filling foundation with burnt stone jelly concrete in mortar.	C.ft.	720	
3	Filling foundation with burnt stone in clay	"	958	
4	Basement, burnt stone in clay	"	642	
5	Superstructure, burnt brick in clay	"	1,463	
6	Do burnt brick in mortar	"	586	
7	Burnt stone slabs 6" thick roughly dressed	S.ft.	360	
8	Teakwood doors pannel 1½" thick plank shutters and 4"×5" thick frames and iron fittings, complete with rectangular ventilators.	"	124	
9	Teakwood windows large, outside panel and inside glazed shutters with rectangular glass ventilators and ¾" iron round bars and iron fillings, etc., complete shutters 1" thick frame 4"×5" thick.	"	234	
10	Teakwood wall Almirah with cross planks and panel shutters 1" thick plank and iron fittings, etc., complete.	"	95	
11	Teakwood work wrought and put up with oiling, etc.	C.ft.	58.71	
12	Roofing with 1st Class Mangalore tiles on 2"×1" teak reepers, etc., complete.	Sqr.	16.72	
13	Ridge tiles set in mortar, Mangalore	R.ft.	81	
14	Teakwood planks, zinc sheets and cement fillets, etc., to valley portions.	S.ft.	105	
15	Teakwood eave board ornamental 10" deep	R.ft.	176	
16	Teakwood finials 3' high	Each	4	
17	Teakwood pendants	"	10	
18	Tarring to wood work 3 coats	Sqr.	4.00	
19	Flooring with 9"×9" square Mangalore clay tiles on 3" concrete bed cement pointing, etc.	"	6.00	

No.	Items of work	Per	Quantity	Rate
				Rs.
20	Flooring with 1½" thick Cuddapah slabs on 3" concrete bed and cement pointing, etc.	Sqr.	3'71	
21	Binding wall over gable. Brick in mud	R.ft.	51	
22	Cut stone pillars 8" × 8" square with base and capitula as per design.	"	64	
23	Plastering with mortar	Sqr.	47'28	
24	Whitewashing 2 coats	"	47'28	
25	Cement pointing to basement	"	3'62	
26	Chocolate painting 3 coat	"	16'63	
27	Teakwood screen with doorway, etc.	S.ft.	98	
28	Counters with teakwood planks and iron fittings, etc., complete.	Each	2	
29	Ornamental work with mortar as per plan below windows and top, etc.	Lump	sum	
30	Sinks in bath room	Each	2	
<i>Construction of quarters for Sub-Assistant Surgeon.</i>				
1	Earthwork excavation foundation and refilling in basement level with consolidation.	C.ft.	87	
2	Burnt stone in clay foundation and basement	"	1,502	
3	Burnt brick in clay, superstructure	"	1,309	
4	Burnt brick in mortar	"	245	
5	Burnt stone slabs, 6" thick roughly dressed	S.ft.	278	
6	Teakwood battened doors 1½" thick plank and iron fitting, etc., complete frame 4" × 5" thick.	"	228	
7	Teakwood windows outside panel and inside glassed shutter with 5/8" iron bars and iron fitting, etc., frame 4" × 5" thick, plank 1" thick.	"	48	
8	Teakwood ventilators with glassed shutter, etc.	"	36	
9	Teakwood work wrought and put up with wood oiling, etc.	C.ft.	53'04	
10	Roofing with 1st Class Mangalore tiles on 2", 1" thick reepers, etc.	Sqr.	12'16	
11	Ridge tiles set in mortar, plain	R.ft.	106	
12	Pucca terrace flat	Sqr.	0'80	
13	Cut stone pillars with base and capitula	R.ft.	24	
14	Chunam plastering	Sqr.	43'17	
15	Whitewashing 2 coats	"	43'17	
16	Flooring with 9" × 9" square Mangalore clay tiles on 3" concrete bed and cement pointing.	"	2'97	
17	Flooring with burnt stone jelly concrete terrace over nice plastering.	"	2'08	
18	Flooring with 1½" thick Cuddapah slabs on 3" concrete bed and cement pointing, etc.	"	1'31	
19	Coping over compound wall	R.ft.	53	
20	Pointing with mortar	Sqr.	2'87	
21	Burnt brick in clay parapet wall, etc.	R.ft.	24½	
22	Cornice work, 9" deep	"	23½	
23	Teakwood eave board (8")	"	190	
24	Chocolate painting 3 coats	Sqr.	10'00	
25	Tarring to wood work 3 coats	"	4'00	
26	Teakwood finials	Each	3	
27	Do pendants	"	10	

No.	Items of work	Per	Quantity	Rate
<i>Construction of a midwife quarters, and Compounder.</i>				
1	Earthwork excavation foundation and filling in basement level, etc.	C.yd.	23	
2	Burnt stone in clay foundation and basement	C.ft.	02	
3	Burnt brick in clay, superstructure	"	817	
4	Do in mortar	"	169	
5	Burnt stone slabs 6" thick	Sq.ft.	126	
6	Teakwood battened doors 1½" thick plank with W. S. T. Hinges 12" long with locking arrangement, etc.	"	93	
7	Teakwood battened windows 1" thick plank and 5/8" iron bars and iron fittings, etc.	"	31½	
8	Teakwood glassed ventilators	"	9	
9	Teakwood work wrought and put up with oiling, etc.	C.ft.	19'41	
10	Roofing with First Class Mangalore tiles on 2" x 1" teak reepers, etc.	Sqr.	5'05	
11	Ridge tiles set in mortar	R.ft.	54	
12	Plastering with mortar	Sqr.	25'00	
13	Whitewashing two coats	"	25'00	
14	Flooring with 1½" thick cuddapha slabs on 3" concrete bed and cement pointing, etc.	"	2'60	
15	Gravel flooring	C.yd.	3	
16	Coping over compound wall	R.ft.	73	
17	Teakwood eave board	"	90	
18	Teakwood finials	Each	2	
19	Teakwood pendants	"	8	
20	Tarring to wood 3 coats	Sqr.	2'00	
21	Chocolate painting 3 coats	"	5'00	
<i>Construction of a Kitchen.</i>				
1	Earthwork excavation foundation and filling in basement level with consolidation.	C.yd.	6	
2	Burnt stone in clay foundation and basement	C.ft.	212	
3	Burnt brick in clay, superstructure	"	229	
4	Do in mortar	"	76	
5	Burnt stone slabs 6" thick roughly dressed	"	29	
6	Teakwood battened doors 1½" thick and W. S. T. Hinges 12" long and locking arrangements, etc.	S.ft.	23	
7	Teakwood battened windows with 5/8" iron bars and iron fitting, etc., complete.	"	9	
8	Teakwood work, wrought and put up with oiling, etc.	C.ft.	5'46	
9	Roofing with First Class Mangalore tiles on 2" x 1" teak reepers, etc.	Sqr.	2'10	
10	Ridge tiles set in mortar	R.ft.	15	
11	Smoke ventilators	Each	2	
12	Plastering with mortar	Sqr.	6'15	
13	Whitewashing 2 coats	"	6'15	
14	Flooring with 3" thick burnt stone slabs on 6" sand bed and cement pointing, etc.	"	70	
15	Teakwood eave board	R.ft.	58	
16	Tarring to wood work 3 coats	Sqr.	1'00	
17	Chocolate painting 3 coats	"	2'00	
<i>Dead House.</i>				
1	Earthwork excavation foundation and filling in basement level, etc.	C.yd.	13	
2	Burnt stone in clay foundation and basement	C.ft.	365	
3	Burnt brick in clay	"	274	
4	Burnt stone slabs 6" thick roughly dressed	S.ft.	72	
5	Burnt slab post one line dressed	"	40	
6	Operation stone slab table 6" thick nicely dressed and cutting grooves at ends, etc.	"	23	

No.	Items of work	Per	Quantity	Rate
7	Teakwood battened doors 1½" thick and W. S. T. Hinges 12" long, etc.	S.ft.	23	
8	Teakwood battened windows 1" thick and 2" iron bar and iron fitting, etc.	"	18	
9	Teakwood work wrought and put up with oiling, etc.	C.ft.	12.11	
10	Roofing with First Class Mangalore tiles on 2" x 1" teak reepers, etc.	Sqr.	3.40	
11	Ridge tiles set in mortar	R.ft.	17	
12	Mangalore ventilators tiles	Each	4	
13	Plastering with mortar	Sqr.	5.00	
14	Whitewashing 2 coats	"	5.00	
15	Flooring with 3" thick burnt stone slabs on 3" concrete bed and cement pointing, etc.	"	1.44	
16	Hony comb work	"	2.19	
17	Tarring to wood work 3 coats	"	2.00	
18	Chocolate painting 3 coats	"	2.39	
19	Teakwood eave board	R.ft.	74	
20	Binding wall	"	34	
21	Pointing with mortar	Sqr.	59	
<i>Latrine.</i>				
1	Earthwork excavation foundation	C.yd.	4	
2	Burnt stone in clay foundation and basement	C.ft.	146	
3	Burnt brick in clay	"	161	
4	Coping with burnt brick in mortar, etc.	R.ft.	39	
5	Plastering with mortar	Sqr.	4.50	
6	Whitewashing 2 coats	"	4.50	
7	Flooring with 3" thick burnt stone slabs on 3" concrete bed and cement pointing, etc.	"	.60	
8	Cut stone seats	Each	2	
<i>Compound Wall.</i>				
1	Compound wall with gate, burnt stone in clay foundation and burnt brick in clay superstructure with coping, plastering, whitewashing, etc., complete. Pilasters 1 1/8' x 1 1/8' Square pannel ¾' high 5½' superstructure, foundation and basement 2' depth and 1½' feet wide.	R.ft.	600	

Notice dated 2nd July 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Bangalore Division, up to 2 P.M., on 20th July 1929, for restoring Gunjur Mavankere of Bangalore Taluk. An approximate estimate of quantities is given below. * These quantities are not guaranteed. The work should be completed by the end of May 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3a. Percentages less or above sanctioned rates will not be accepted.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Restoring Gunjur Mavankere" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of quantities for Gunjur Mavankere Tank, Regd. No. 208, Bangalore Taluk.

No.	Items of work	Quantity	Per	Rate
	<i>Bund R. L. 55'00 and top width 6 feet.</i>			Rs. a. p.
1	Cutting grips and clearing jungle ...	22	Grade	
2	Earthwork to bund with watering and tamping-including lead and lift.	4,930	Cyds.	
3	Turfing the slopes ...	6,349	S.yd.	
4	New stone revetment ...	179	C.yd.	
5	Resetting old stone work ...	136	"	
6	Providing new grade stones with figuring and painting	23	Each	
7	Do Index stones do ...	23	"	
8	Do Register No. stone do ..	1	"	
9	Do B. M. stones do ...	2	"	
10	Do Gauge stone do ...	1	"	
	<i>Sluices.</i>			
1	Repairing the right sluice with locking arrangements	Lump sum		
2	Do Left sluice do ...	"	"	
	<i>Extending Left Waste Weir towards right to a total length of 400 feet.</i>			
1	Earthwork ...	582	C.yds.	
2	Burnt brick in surki mortar ...	1,083	C.ft.	
3	Plastering with surki mortar ...	10'95	Sqr.	
4	Burnt stone slabs dressed ...	530	S.ft.	
5	Rough stone work apron new ...	461	C.yds.	
6	Do Revetment ...	9	"	
7	Stone in surki martar ...	81	C.ft.	
	<i>Raising the existing weir from R. L. 50'00 to 51'00 and 54 feet.</i>			
1	Burnt brick in surki mortar ...	90	C.ft.	
2	Removing and refixing coping slabs ...	90	S.ft.	
3	Plastering with surki mortar ...	1'08	Sqr.	
4	Concrete in surki mortar ...	81	C.ft.	
5	Jelly packing to rough stone apron ...	13'50	Sqr.	
	<i>Raising the road to R. L. 53'00.</i>			
1	Earthwork embankment with lead and lift ...	1,580	C.yds.	
2	Turfing the slopes ...	803	S.yds.	
3	Collection of metal with lead ...	242	C.yds.	
4	Do gravel do ...	121	"	
5	Spreading and consolidating metal ...	242	"	
6	Do gravel ...	121	"	
7	Do sand ...	17	"	
8	Sundry repairs to tunnel ...	3	Each	

H. R. VENKATASUBBA RAO,
Executive Engineer.